



The Complete Solution

5/13/2016

Leah

Front Range Airport

5200 Front Range Pkwy.

Watkins, CO 80137

*Quote
2016.302*

PROJECT: AST Installation

SUBJECT: AST Installation

Dear Leah,

Please find enclosed the proposal developed for your project based on our understanding of your needs at this time. We appreciate the opportunity to submit this proposal for your consideration. Included in this quotation are descriptions and prices for equipment at your jobsite and pertinent terms, exclusions and conditions. If the equipment quoted, or the scope of work differs from your specifications, we will be happy to modify this proposal as required.

Thank you for the opportunity to be of service to you. We at Seneca sincerely appreciate your business. If there is any additional information that you would like concerning this quotation, please do not hesitate to call me at 303-744-2125. I look forward to working with you on this project.

Sincerely,

Scott Marr
Petroleum Equipment Representative
Seneca Companies

EQUIPMENT

DISPENSING EQUIPMENT

- 1 Gasboy Electronic Commercial Atlas 9840KX Super-Hi -
Single Dispenser - Side Load

Image Standard Option - Black Top & Sides, White Lower,
Brand Panel A Side Description DYED DIESEL, Internal
Filters Standard 30 Micron, Electro Mechanical Accum.
Totalizer Gallons Card Interface Single Pulse Output,
Support Post Universal (047028).

- 1 FE Petro STP-75 VL2 3/4 Horsepower Submersible Pump
- 1 FE Petro 400818921 Single Phase Controller ***
- 1 Morrison #710 0200 1V 2" Solenoid Valve ***
- 1 Morrison #346DI 0500 AV 2" External Emergency Valve
- 1 OPW 10BU-5925 1 1/2" Shear Valve
- 1 Graco HSLE3B 1" x 30' XD Series Fuel Hose Reel.

DISPENSING EQUIPMENT TOTAL

\$9,013.23

DISPENSING ACCESSORIES

- 1 FDP 1 Pint E-Seal Gasoila
- 1 HUS 1" MxF Swivel
- 1 HUS 1" Recon Safe-Break
- 1 IRP 1"x10" Whip Hose
- 1 IRP 1"x17' SW 4S Hose
- 1 OPW 7HB-0100 Green High Flow Nozzle

DISPENSING ACCESSORIES TOTAL

\$336.49

DISPENSER SUMPS

- 1 APT SBK-25 Stabilizer Bar Kit

DISPENSER SUMPS TOTAL

\$47.42

ABOVEGROUND STORAGE TANKS

- 1 WeMac Mfg. SC-D 414-D 2K UL2085 AST w/ Skids.
- 2 Morrison #244O 0200 AV 6" 8oz Emergency Vent, Female Threaded ***
- 1 Morrison 155-0500 AV 2" Tee Vent ***
- 1 Morrison #918 0100 AG 2" Clock Gauge, Alarm w/ Float ***
- 1 Morrison #9095A A3300 AV 3" AST Overfill Prevention Valve ***
- 1 Morrison #419 0200 1T 3" x 10' Aluminum Drop Tube ***
- 1 Morrison #515 0200 AC 2" AST Remote Spill Container
- 1 Morrison #246A 0200 AV 2" Horizontal Swing Check Valve ***
- 1 Morrison #691B 0800 1V 2" Full Port Locking Ball Valve ***
- 1 Morrison #800F 0400 1C 2" Part F Male Adapter, Male Thread ***
- 1 Morrison #800DC 0400 1C 4" Dust Cap ***
- 1 Krueger K-2-64 Leak Gauge ***
- 1 Misc. Black Pipe and Fittings for Fills, Supply and Vents.
- 1 Misc. Unistrut, Clamps, Bolts and Fastners for Fill and Supply.
- 1 Bravo Dispenser Sump Box B-8600-1PM-B

ABOVEGROUND STORAGE TANKS TOTAL

\$16,209.47

PRODUCT & VENT PIPING

- 1 APT FEB-175-SC Flexible Entry Boot, 1 3/4" Transition Sump Product

	PRODUCT & VENT PIPING TOTAL	\$42.62
	PIPING MATERIALS	
1	Miscellaneous 2" Pipe Fittings to Plumb Dispenser	
	PIPING MATERIALS TOTAL	\$152.58
	EQUIPMENT TOTAL	\$ 25,801.82

INSTALLATION

PROPOSED SERVICES TO BE PERFORMED BY SENECA

Set Barricades-we will take every precaution to ensure safety by placing barricades throughout our work space

CON Drive Time

Trenching for Electrical Conduit

Installation of tank fittings (Includes overfill prevention valves and spill prevention)

Installation of 1 submersible pump.

Air Testing of Tank and Product Piping.

Installation of hanging hardware - nozzles, hoses & purge, calibrate and caulk each dispenser.

Purge and Calibrate the Dispenser.

SVC Drive Time

SENECA WILL SUPERVISE THE FOLLOWING ACTIVITIES

Electrical installation of petroleum equipment. -to be performed during manufacturers support desk business hours 8:00 am to 5:00 pm.

OWNER IS RESPONSIBLE FOR THE FOLLOWING ACTIVITIES

City or County Permits/Inspections

LABOR AND MATERIAL TOTAL \$ **31,438.94**

FREIGHT TOTAL \$ **453.18**

GRAND TOTAL \$ **57,693.94**

DOES NOT INCLUDE APPLICABLE TAXES

TERMS AND CONDITIONS